



Builder checklist for appliance delivery & installation

- Entry steps are ready so the appliances can be moved into the house.
- Crew has clear access to move appliances into the site.
- Floor protection is available. Crews will bring additional floor protection, but every bit helps.
- Electrical supply is in the proper location according to the specs, and cover plates are installed.
- Plumbing is finished behind washers or under the sink for dishwashers and disposals, so appliances can be connected and tested.
- Countertops are installed prior to crew arrival.
- Venting is in run for the hood and is located in the proper location for the connection.
- Venting is the proper size, according to the specs.
- Wall/ceiling has adequate blocking and support for wall/island hoods.
- Cabinets are built to the proper specs for refrigerator/freezer. Cabinets are flush and finished on the inside, both sides and top from the face of the cabinet to 6 inches back.
- Refrigerator water line is in the proper location.
- All custom panels and handles are on site and handle height has been determined and clearly communicated.
- Cabinets are deep enough for built-in ovens. Often, the builder has to cut into the wall to accommodate.
- Adequate space is available for oven electrical supply.
- Electric and gas supply lines are in the proper location for ranges & cooktops, according to the specs.
- Electrical and gas supply lines are on/live so the crew can test units.
- Supervisor will be on site to direct and communicate.

Warners' Stellian crews reconnect appliances; we cannot modify facilities.
Thank you for having everything ready!